

DA699

Delayed mains fail detector unit
 With 30 seconds delay

Mains fail and fault indicator which will trigger 30 seconds after a power failure.

Switching contacts

Contact configuration	Single pole
Voltage	Maximum 30V DC
Current	Maximum 1A
Connection type	PCB terminal block (2.5mm ²)

Indicators

Mains fail	LED indication
Mains fault	LED indication

Input

Voltage	12V DC
Power consumption	< 20VA
Connection type	850mm fly-lead

Environmental

Operating temperature	-10°C to +40°C
Storage temperature	-20°C to +50°C
Operating relative humidity	Maximum 95% non-condensing

Dimensions*

Width	90mm
Height	50mm
Depth	20mm
Weight	< 0.08Kg
Enclosure material	Plastic
Finish	White

Other

Estimated mean time before failure (MTBF)	50,000 hours
CE Approved	Yes
Lid tamper switch	Yes

*(+/- 2mm)